

HO-113

## Bernard Warfield Farm (The Heritage, Bite the Skinner)

### **Architectural Survey File**

This is the architectural survey file for this MIHP record. The survey file is organized reverse-chronological (that is, with the latest material on top). It contains all MIHP inventory forms, National Register nomination forms, determinations of eligibility (DOE) forms, and accompanying documentation such as photographs and maps.

Users should be aware that additional undigitized material about this property may be found in on-site architectural reports, copies of HABS/HAER or other documentation, drawings, and the “vertical files” at the MHT Library in Crownsville. The vertical files may include newspaper clippings, field notes, draft versions of forms and architectural reports, photographs, maps, and drawings. Researchers who need a thorough understanding of this property should plan to visit the MHT Library as part of their research project; look at the MHT web site ([mht.maryland.gov](http://mht.maryland.gov)) for details about how to make an appointment.

All material is property of the Maryland Historical Trust.

***Last Updated: 02-07-2013***

H0-113

The Bernard Warfield House  
Woodbine  
Private

1812

The Bernard Warfield House faces south on the south east corner of Route 94 and Mullinix Road. It is a five bay wide, one room deep two and a half story high, gabled roof (running east-west) brick bond building, laid on a fieldstone foundation with wide brick chimneys inset into its east and west walls.

The central, rectangular double door is located on the south elevation. It is surmounted by a four light transom and stretcher brick flat arched lintel, flanked by two rectangular, double hung first floor windows, holding nine-over-six lights, decorated with projecting wooden sills and stretcher brick, flat arched lintels. Fenestration is vertically aligned and proportionally scaled with second floor windows on the south facade (laid in flemish bond) holding six-over-six lights. Three gabled roof dormers rest above.

An office-den-kitchen two story high, intersecting gabled roof (running north-south) brick and stucco north wing creates an "L" plan off the west side of the building's north wall.

A one story high, gabled roof (running north-south) brick (laid in English garden wall brick bond) smokehouse stands north of the house, and large barn and auxiliary buildings east and south.

Notable as a Warfield Farm for over a century, it is most significant as the farm of the son of J.D. Warfield, local historian of Howard County, who wrote Founders of Anne Arundel and Howard Counties, Maryland.

## INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

**1 NAME**

HISTORIC

Bite the Skinner (The Heritage)

AND/OR COMMON

The Bernard Warfield Farm

**2 LOCATION**

STREET &amp; NUMBER

Southeast corner of Mullinex Road and Route 94

CITY, TOWN

Woodbine

VICINITY OF

CONGRESSIONAL DISTRICT

6th

STATE

Maryland

COUNTY

Howard

**3 CLASSIFICATION**

CATEGORY

☒ DISTRICT☐ BUILDING(S)☐ STRUCTURE☐ SITE☐ OBJECT

OWNERSHIP

☐ PUBLIC☒ PRIVATE☐ BOTH

PUBLIC ACQUISITION

☐ IN PROCESS☐ BEING CONSIDERED

STATUS

☐ OCCUPIED☐ UNOCCUPIED☒ WORK IN PROGRESS☒ ACCESSIBLE☐ YES: RESTRICTED☐ YES: UNRESTRICTED☐ NO

PRESENT USE

☒ AGRICULTURE☐ COMMERCIAL☐ EDUCATIONAL☐ ENTERTAINMENT☐ GOVERNMENT☐ INDUSTRIAL☐ MILITARY☐ MUSEUM☐ PARK☒ PRIVATE RESIDENCE☐ RELIGIOUS☐ SCIENTIFIC☐ TRANSPORTATION☐ OTHER**4 OWNER OF PROPERTY**

NAME

Mr. and Mrs. Donald Warfield

Telephone #: 489-4683

STREET &amp; NUMBER

Northeast corner of Mullinex Road and Route 94

CITY, TOWN

Woodbine

VICINITY OF

STATE, zip code  
Maryland 21797**5 LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE.

REGISTRY OF DEEDS, ETC.

Tax Map 7 p.132

Hall of Records

Liber #: 107 402

Folio #: 563 570

STREET &amp; NUMBER

Howard County Court House

CITY, TOWN

Ellicott City

STATE

Maryland

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE

Howard County Historic Sites Inventory

DATE

1978-1979

☐ FEDERAL ☒ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR  
SURVEY RECORDS

Maryland Historical Trust

CITY, TOWN

21 State Circle, Annapolis

STATE

Maryland

CONDITION		CHECK ONE	CHECK ONE
<input checked="" type="checkbox"/> EXCELLENT	<input type="checkbox"/> DETERIORATED	<input type="checkbox"/> UNALTERED	<input checked="" type="checkbox"/> ORIGINAL SITE
<input type="checkbox"/> GOOD	<input type="checkbox"/> RUINS	<input checked="" type="checkbox"/> ALTERED	<input type="checkbox"/> MOVED DATE _____
<input type="checkbox"/> FAIR	<input type="checkbox"/> UNEXPOSED		

## DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Bernard Warfield Farm faces south on the south east corner of Route 94 and The Mullinex Road. It is a five bay wide, one room deep, two and a half story, gabled roof (running east - west) brick (laid in flemish bond and English garden wall brick bond) structure laid on a field stone foundation, with wide brick chimneys inset into its east and west walls.

The central, rectangular double door is located on the south elevation. It is surmounted by a four light transom and stretcher brick flat arched lintel, flanked by two rectangular, double-hung first floor windows, holding nine-over-six lights, decorated with projecting wooden sills and stretcher brick, flat arched lintels.

Fenestration is vertically aligned and proportionally scaled. The south elevation is laid in flemish bond and holds five second floor windows similar to those below. The second floor windows hold six-over-six lights and are similarly decorated to the others. Three gabled roof dormer windows rest above. They hold single, rectangular, double-hung windows with six-over-six lights. A plain wooden cornice decorates the roof line on this elevation.

The west elevation of the main body of the house holds a nine-over-nine light first floor window in the north bay, decorated with a stretcher brick flat arched lintel, which is vertically aligned to a nine-over-six light second floor window decorated with a flat header brick lintel. Two square casement, four light, attic windows, decorated with header brick flat lintels rest above.

The east elevation holds a wide batten wood rectangular cellar entrance surmounted by a hand hewn flat wooden lintel. It is flanked by a stone retaining wall, covered by a gabled roof. No first and second floor windows appear on this elevation but two four light attic casement windows rest in the A line formed by the gable roof. They are underlined by projecting wooden sills, flanked by flat pilasters and surmounted by flat wooden lintels.

The north elevation holds two vertically aligned and proportionally scaled first and second floor windows in the two east bays of the north wall. A square cellar window rests in the stone foundation between and below these windows. The interior central entrance hall holds a rectangular north entrance. This has become a door leading into the office-den running along the central and two west bays of the north wall of the main house. This

CONTINUE ON SEPARATE SHEET IF NECESSARY

Description (Con't)

kitchen-den wing forms an "L" plan and is now a three bay wide, one room deep, two story high, intersecting gable roof (running north-south) brick (laid in English garden wall brick bond) first floor and stuccoed second floor structure. A tall square, brick chimney rises from the gable roof between the central and south bays of the west wall. Fenestration for this section of the house is rectangular, double-hung, holding six-over-six lights. This section, too, rests on a field stone foundation. The west wall appears to have been repaired in several places, indicating a possible earlier construction date than the rest of the house. The lintels of the three first floor windows, of which the central one has been blocked in for better interior arrangement, are surmounted by header brick flat lintels. The second floor appears constructed of frame which has been covered with stucco. These windows are underlined by projecting wooden sills, flanked by flat pilasters and surmounted by flat wooden lintels.

The north elevation of this section of the house holds a blocked entrance and west of it a rectangular six-over-six light window. A wide exterior stone foundation centered on this wall may once have been the base for a wide cooking fire place which was later removed. The brick fill in this central section of the wall substantiates such a theory.

What was once a one story high, shed roofed kitchen porch along the east elevation of this section of the house has been enclosed and built on a cinder block foundation. A second floor has been added on the south side beneath which is located the den. The space above is used as a bath, with six-over-six light north window. Below rests a den double window, each component similar to the window above.

Eight cement steps lead to the rectangular kitchen entrance on the east wall. Two four-over-four light first floor windows rest north of the door.

A one story high, squarish, gabled roof (running north-south) brick (laid in English garden wall brick bond) smoke house, laid on a stone foundation, lies north of the house. It holds a central rectangular batten wood door on its east wall, surmounted by a flat wooden lintel.

**8 SIGNIFICANCE**

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION		<b>local history</b>	

SPECIFIC DATES    1812

BUILDER/ARCHITECT

## STATEMENT OF SIGNIFICANCE

The Bernhard Warfield House, known as The Heritage and once as Locust Grove, stands on a part of Philamon Dorsey Warfield's holdings, known as Bite the Skinner. It is architecturally and historically significant to Howard County and the State of Maryland as a fine example of an early brick five bay wide, one bay deep, central hall, gabled roof domicile and as the home of Philemon Dorsey Warfield, Son of Captain Benjamin Warfield of Cherry Grove, who served as a lieutenant in the War of 1812. On returning from that war he married Lucretia Welsh, daughter of Philip Welsh, one of the early settlers of the Florence area.

Here they raised eleven children, among whom was J. D. Warfield, author of Founders of Anne Arundel and Howard Counties, Maryland, the bible for all interested in historical research in Howard County. In addition he served as head master and English teacher at Brookville Academy and later at the Glenwood Institute before becoming a professor at the University of Maryland, then known as the Maryland Agricultural College. It is presently owned by the great grandson of Philemon and grandson of Professor Warfield, Mr. David Warfield.

Architecturally, it is notable as one of Howard County's few brick federal homes, featuring fine flemish bond brick on its main facade and wide brick chimneys inset into its end walls with a dining room-kitchen intersecting gabled roof wing creating an "L" plan.

An old brick smoke house of this early period stands near the house as well as a large barn and auxiliary buildings.

In the process of being totally renovated, it is one of Howard County's finest landmarks, one of some thirty sites chosen by local historian, Celia Holland in her bicentennial edition of Landmarks of Howard County, Maryland.

Historically and architecturally of outstanding merit, this house and its surrounding outbuildings should be placed on the National Register of Historic Sites.

CONTINUE ON SEPARATE SHEET IF NECESSARY



## 9 MAJOR BIBLIOGRAPHICAL REFERENCES

Holland, Celia Howard County Landmarks

College Park 1976

Interview with Mrs. Donald Warfield, August 29, 1978

CONTINUE ON SEPARATE SHEET IF NECESSARY

## 10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 53.11 p.132

Please see Attachment 1

Tax Map 7 p PAR 1

### VERBAL BOUNDARY DESCRIPTION

Please see Howard County Land Records Liber 107, folio 563

### LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE Maryland

COUNTY Howard

STATE

COUNTY

## 11 FORM PREPARED BY

NAME / TITLE

Cleora Barnes Thompson, Archivist

ORGANIZATION

Office of Planning & Zoning-Comprehensive Planning Section

DATE

465-5000 x257

STREET & NUMBER

3450 Court House Drive

TELEPHONE

CITY OR TOWN

Ellicott City

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust  
The Shaw House, 21 State Circle  
Annapolis, Maryland 21401  
(301) 267-1438

## INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

**1 NAME**

HISTORIC

Bite the Skinner (The Heritage)

AND/OR COMMON

The Bernard Warfield Farm

**2 LOCATION**

STREET &amp; NUMBER

South side of Mullinex Road, About .4 mile  
Southeast corner of Mullinex Road and Route 94 Southeast of

CITY, TOWN

Woodbine

VICINITY OF

Lisbon

CONGRESSIONAL DISTRICT

(6th)

STATE

Maryland

COUNTY

Howard

**3 CLASSIFICATION****CATEGORY**☒ DISTRICT  
☒ BUILDING(S)  
☐ STRUCTURE  
☐ SITE  
☐ OBJECT**OWNERSHIP**☒ PUBLIC  
☒ PRIVATE☐ BOTH**PUBLIC ACQUISITION**☐ IN PROCESS  
☐ BEING CONSIDERED**STATUS**☐ OCCUPIED  
☐ UNOCCUPIED  
☒ WORK IN PROGRESS  
☒ ACCESSIBLE  
☒ YES RESTRICTED  
☐ YES UNRESTRICTED  
☐ NO**PRESENT USE**☒ AGRICULTURE  
☐ COMMERCIAL  
☐ EDUCATIONAL  
☐ ENTERTAINMENT  
☐ GOVERNMENT  
☐ INDUSTRIAL  
☐ MILITARY  
☐ MUSEUM  
☐ PARK  
☒ PRIVATE RESIDENCE  
☐ RELIGIOUS  
☐ SCIENTIFIC  
☐ TRANSPORTATION  
☐ OTHER**4 OWNER OF PROPERTY**

NAME

Mr. and Mrs. Donald Warfield

Telephone #: 489-4683

STREET &amp; NUMBER

~~Northeast corner of Mullinex Road and Route 94~~ 1999 Route 94

CITY, TOWN

Woodbine

VICINITY OF

STATE, zip code  
Maryland 21797**5 LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE

Tax Map 7 p.132

REGISTRY OF DEEDS, ETC

Hall of Records

Liber #: 107 402

Folio #: 563 570

STREET &amp; NUMBER

Howard County Court House

CITY, TOWN

Ellicott City

STATE

Maryland

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE

~~Howard County Historic Sites Inventory~~

DATE

1978-1979

~~FEDERAL~~ ☒ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR  
SURVEY RECORDS~~Maryland Historical Trust~~

CITY, TOWN

21 State Circle, Annapolis

STATE

Maryland



# DESCRIPTION

HO-113

District 4

## CONDITION

☒ EXCELLENT  
☐ GOOD  
☐ FAIR

☐ DETERIORATED  
☐ RUINS  
☐ UNEXPOSED

## CHECK ONE

☒ UNALTERED  
☐ ALTERED

## CHECK ONE

☒ ORIGINAL SITE  
☐ MOVED DATE \_\_\_\_\_

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Bernard Warfield Farm faces south on the south east corner of Route 94 and The Mullinex Road. It is a five bay wide, one room deep, two and a half story, gabled roof (running east - west) brick (laid in flemish bond and English garden wall brick bond) structure laid on a field stone foundation, with wide brick chimneys inset into its east and west walls.

The central, rectangular double door is located on the south elevation. It is surmounted by a four light transom and stretcher brick flat arched lintel, flanked by two rectangular, double-hung first floor windows, holding nine-over-six lights, decorated with projecting wooden sills and stretcher brick, flat arched lintels.

Fenestration is vertically aligned and proportionally scaled. The south elevation is laid in flemish bond and holds five second floor windows similar to those below. The second floor windows hold six-over-six lights and are similarly decorated to the others. Three gabled roof dormer windows rest above. They hold single, rectangular, double-hung windows with six-over-six lights. A plain wooden cornice decorates the roof line on this elevation.

The west elevation of the main body of the house holds a nine-over-nine light first floor window in the north bay, decorated with a stretcher brick flat arched lintel, which is vertically aligned to a nine-over-six light second floor window decorated with a flat header brick lintel. Two square casement, four light, attic windows, decorated with header brick flat lintels rest above.

The east elevation holds a wide batten wood rectangular cellar entrance surmounted by a hand hewn flat wooden lintel. It is flanked by a stone retaining wall, covered by a gabled roof. No first and second floor windows appear on this elevation but two four light attic casement windows rest in the A line formed by the gable roof. They are underlined by projecting wooden sills, flanked by flat pilasters and surmounted by flat wooden lintels.

The north elevation holds two vertically aligned and proportionally scaled first and second floor windows in the two east bays of the north wall. A square cellar window rests in the stone foundation between and below these windows. The interior central entrance hall holds a rectangular north entrance. This has become a door leading into the office-den running along the central and two west bays of the north wall of the main house. This

CONTINUE ON SEPARATE SHEET IF NECESSARY

Description (Con't)

kitchen-den wing forms an "L" plan and is now a three bay wide, one room deep, two story high, intersecting gable roof (running north-south) brick (laid in English garden wall brick bond) first floor and stuccoed second floor structure. A tall square, brick chimney rises from the gable roof between the central and south bays of the west wall. Fenestration for this section of the house is rectangular, double-hung, holding six-over-six lights. This section, too, rests on a field stone foundation. The west wall appears to have been repaired in several places, indicating a possible earlier construction date than the rest of the house. The lintels of the three first floor windows, of which the central one has been blocked in for better interior arrangement, are surmounted by header brick flat lintels. The second floor appears constructed of frame which has been covered with stucco. These windows are underlined by projecting wooden sills, flanked by flat pilasters and surmounted by flat wooden lintels.

The north elevation of this section of the house holds a blocked entrance and west of it a rectangular six-over-six light window. A wide exterior stone foundation centered on this wall may once have been the base for a wide cooking fire place which was later removed. The brick fill in this central section of the wall substantiates such a theory.

What was once a one story high, shed roofed kitchen porch along the east elevation of this section of the house has been enclosed and built on a cinder block foundation. A second floor has been added on the south side beneath which is located the den. The space above is used as a bath, with six-over-six light north window. Below rests a den double window, each component similar to the window above.

Eight cement steps lead to the rectangular kitchen entrance on the east wall. Two four-over-four light first floor windows rest north of the door.

A one story high, squarish, gabled roof (running north-south) brick (laid in English garden wall brick bond) smoke house, laid on a stone foundation, lies north of the house. It holds a central rectangular batten wood door on its east wall, surmounted by a flat wooden lintel.

Attachments:

Floor Plan

Listing of color slides and 5"x7" black and white photos

## SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)
				local history

SPECIFIC DATES 1812

BUILDER/ARCHITECT

## STATEMENT OF SIGNIFICANCE

The Bernhard Warfield House, known as The Heritage and once as Locust Grove, stands on a part of Philamon Dorsey Warfield's holdings, known as Bite the Skinner. It is architecturally and historically significant to Howard County and the State of Maryland as a fine example of an early brick five bay wide, one bay deep, central hall, gabled roof domicile and as the home of Philemon Dorsey Warfield, Son of Captain Benjamin Warfield of Cherry Grove, who served as a lieutenant in the War of 1812. On returning from that war he married Lucretia Welsh, daughter of Philip Welsh, one of the early settlers of the Florence area.

Here they raised eleven children, among whom was J. D. Warfield, author of Founders of Anne Arundel and Howard Counties, Maryland, the bible for all interested in historical research in Howard County. In addition he served as head master and English teacher at Brookville Academy and later at the Glenwood Institute before becoming a professor at the University of Maryland, then known as the Maryland Agricultural College. It is presently owned by the great grandson of Philemon and grandson of Professor Warfield, Mr. Donald Warfield.

Architecturally, it is notable as one of Howard County's few brick federal homes, featuring fine flemish bond brick on its main facade and wide brick chimneys inset into its end walls with a dining room-kitchen intersecting gabled roof wing creating an "L" plan.

An old brick smoke house of this early period stands near the house as well as a large barn and auxiliary buildings.

In the process of being totally renovated, it is one of Howard County's finest landmarks, one of some thirty sites chosen by local historian, Celia Holland in her bicentennial edition of Landmarks of Howard County, Maryland.

Historically and architecturally of outstanding merit, this house and its surrounding outbuildings should be placed on the National Register of Historic Sites.

CONTINUE ON SEPARATE SHEET IF NECESSARY



**9 MAJOR BIBLIOGRAPHICAL REFERENCES**

Holland, Celia Howard County Landmarks

College Park 1976

Interview with Mrs. Donald Warfield, August 29, 1978

CONTINUE ON SEPARATE SHEET IF NECESSARY

**10 GEOGRAPHICAL DATA**

ACREAGE OF NOMINATED PROPERTY 53.11 p.132

Please see Attachment 1

Tax Map 7 p PAR 1

VERBAL BOUNDARY DESCRIPTION

Attachment from will of Bernard D. Warfield  
Includes farm buildings adjacent meadows and family  
burial ground.

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE Maryland

COUNTY Howard

STATE

COUNTY

**11 FORM PREPARED BY**

NAME / TITLE

Cleora Barnes Thompson, Archivist

ORGANIZATION

Office of Planning & Zoning-Comprehensive Planning Section / 465-5000 x257

DATE (301)

STREET & NUMBER

3450 Court House Drive

TELEPHONE

CITY OR TOWN

Ellicott City

STATE

Maryland 21043

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust  
The Shaw House, 21 State Circle  
Annapolis, Maryland 21401  
(301) 267-1438

HO-113

RA

RECEIVED

FEB 21 1980

MARYLAND HISTORICAL  
TRUST

TO: Maryland Historical Trust  
Shaw House, 21 State Circle  
Annapolis, Md.

From: Mrs Mary Jane Warfield

Re: National Register Form Preparation  
Bernard Warfield Farm  
Howard County HO-113

In response to your request for further information I am including an Interior Description, Acreage and Justification, Verbal boundry and Sketch Map.

In regard to the title search I found recorded in the Md. Hall of Records in Annapolis the deed recording the sale of the tract of land called "Bite the Skinner", 140 acres and one square perch of land more or less, from Charles Greenberry Ridgely to Benjamin Warfield for the sum of 561 pounds, 15 shillings on June 4, 1802. Recorded in Land Records Volume NH No 11 page 599.

"Captain Benjamin Warfield built his home Cherry Grove in 1768. He was commissioned in 1778 a captain in the Elk Ridge Battalion of Militia. Two sons, Beale and Philomen Dorsey Warfield entered the War of 1812. In the midst of that war, in 1814, Captain Benjamin died, leaving the land purchased from Charles G. Ridgely to his son Philomen."

"In 1815 Philomen D. Warfield married Lucretia Welsh and built his brick house "Locust Grove" near the Ridgely pioneer cottage."

The remains of that log structure still stand most of it having recently been leveled by fire.

The family graveyard lies about 250 feet south of the house. It is surrounded by an old iron fence and two rows of cedar trees. It includes the graves of Philomen and Lucretia Warfield and several of their children, including Joshua D. Warfield.

Reference: "Founders of Anne Arundel and Howard Counties" by Joshua D. Warfield.

Considering Joshua D. Warfield was the son of the builder of Locust Grove I think his references should be considered reliable.

Re: Bernard Warfield Farm

NO-113

### Interior Description

First Floor: Central hall, four rooms plus laundry and bath

Second Floor: Four bedrooms and two baths

Third Floor: Two Bedrooms

The main entrance is through double paneled doors beneath a four light transom, and the wide jambs are paneled. This leads to a central hall bounded on the right by a 14 inch thick interior brick wall supported by a field stone foundation.

To the left is an open staircase rising to the third floor. There are eleven steps to the first landing and a returning flight of five steps to the second floor landing. At the first landing there are also three steps leading to the second floor rooms which were added over the rear wing of the house. The staircase continues past the second floor landing for seven steps to a landing and a return flight of seven steps to the third floor. The risers, treads and rectangular balusters are of pine surmounted by an octagonal hand rail of walnut. The turned newel post on the main floor has a 6 $\frac{1}{2}$  inch square base and those above are 4 inch bases. The handrail, main floor newel post and stair treads have remained in a natural finish with all other trim and doors painted.

To the right of the central hall on the main floor is a 16X 20 foot parlor. There are four nine-over-six light windows, two on the front wall and two on the rear wall. Centered on the wall opposite the parlor entry is the fireplace. The pine mantel is supported by flat pilasters with horizontal mouldings above the fireplace opening, which match the window sill mouldings in this room. Window and door trim in the parlor and hall is wider than in the other rooms.

To the left of the hall is a 14 X 20 foot dining room. Centered on the opposite wall is a fireplace with pine mantel. To the right of the fireplace is a nine-over-nine light window and there are two nine-over-six light windows on the front wall. There is a door to the basement stairs next to the rear wall and a door to the kitchen in the rear wall.

All of the floors in the parlor, hall and dining room are four to six inch random width tongue and groove pine and the ceilings nine foot six inches high. The doors are all six panel pine doors.

From the central hall opposite the front entrance there is a door leading to the kitchen. This was at one time an outside back porch entrance but in about 1930 was enclosed to enlarge what is now a 22 X 13 foot kitchen. It has just been remodeled to include six hand hewn beams taken from an older log building on the farm. Beyond the kitchen to the rear is a small den panelled in weathered gray siding, a recently added bay window and fireplace. Adjoining this is a laundry room, a small bathroom and an enclosed stairs leading to the two rooms and bath over the rear wing.



Interior description Continued.

On the second floor in the main wing of the house there are two bedrooms over the parlor and dining rooms. Both rooms have fireplaces with pine mantels and window placement like the rooms beneath them. The windows are six-over-six lights and the ceilings are 8 foot 6 inches, floors are 4 to 6 inch random width pine. A bathroom has been added in the front hall between these two bedrooms; and closets have been added in the bedrooms.

Directly above the second floor front rooms are two finished attic rooms with a dormer window and two casement windows in each. The small hall area between these also has a dormer and 4 to 6 inch pine floors. Bedrooms here are floored in very wide pine and oak boards.

HO-113

RE: Bernard Warfield Farm  
Howard County  
HO-113

Verbal Boundry Description

The plot of land consists of approximately 2½ acres Beginning south east corner following a board fence west- 565 feet to a woven wire fence north 180 feet to a board fence east 609 feet to a board fence bordering A.E. Mullinix Rd. south 195 feet to starting point.

The plot includes the bank barn the brick house and meat house, a machinery shed, and two car garage built in 1940. The bank barn was built in 1918.

There is a family grave yard south of the house about 205 feet.

Mailing Address 16539 A. E. Mullinix Rd  
Woodbine, Md. 21797

H0-113  
1401137984

Bernard Warfield Farm - historic  
Mullinix Rd. - common

2-story brick Federal house -  
Neat farm -

located in Field by MMS - 7/21/70

for Map #7

Bernard D. Warfield  
Josephine D. Warfield

402/570


215.19 A.

p.132

BITE THE SKINNER  
HOWARD COUNTY


HO-113


FLOOR PLAN-FIRST FLOOR



HO-113  
Bernard Warfield Farm  
Howard County

House, Buildings on 2½ acres





40-113

Attachment I  
H0-113  
The Bernard Warfield  
House (The Heritage)  
Tax Maps 7 and 13

BERNARD WARFIELD  
FARM  
53.113 ACRES

2 1/2 ACRES

EFFIE POOLE, L/E  
497/529, 532  
54.87A.  
P.22

LARVE BECRAFT  
497/525, 497/527  
130.62A.  
P.23

ED. W. CRAWFORD  
524/418  
23.06A.  
P.140

A. L. LARIMORE  
425/136  
18.00A.  
P.124

LEROY L.  
256  
132  
P.

JAMES F. MORNINGSTAR, JR.  
541/619  
18.49A.  
P.323

WM. L. PUGH  
622/13  
18.40A.  
P.377

LAWRENCE F. LINDEN  
717/764  
17.87A  
P.392

JOHN W. SCHULER  
742/414  
5.69A  
P.397

KARL T. LEONHARDT  
701/82  
24.50A.  
P.237

SLAGLE  
579/135  
5.00A  
P.185

WM. T. CUMBERLAND  
654/338  
21.08A.  
P.30

4-18A.  
P.171  
17.1  
P.2

P.299


C. MILTON JAYCOX PROP. 43409


FLORENCE

COLONIAL

HARDY







Attachment 2  
H0-113  
The Bernard Warfield House  
(The Heritage)  
U.S. Geological Survey Map  
Woodbine, Maryland Quadrangle  
Scale 1:24000



BITE THE SKINNER H O-113 #1  
HOWARD COUNTY

FRONT VIEW FACING SOUTH

PORCH ADDED 20TH CENTURY

TAKEN BY DONALD B. WARFIELD

4-10-79





BITE THE SKINNER HC-113

HOWARD COUNTY

EAST VIEW

# 2

TAKEN BY DONALD B. WARFIELD

4-10-79





BITE THE SKINNER

HO-113

HOWARD COUNTY

#3

EAST SIDE CELLAR ENTRANCE

TAKEN BY DONALD B WARFIELD

4-10-79



HO-113

BITE THE SKINNER  
HOWARD COUNTY

FACING WEST #4

TAKEN BY DONALD B. WARFIELD

4-10-79



BITE THE SKINNER  
HOWARD COUNTY

HO-113

FRONT ENTRANCE FROM  
CENTER HALL

#5

TAKEN BY DONALD B WARFIELD

APRIL 10, 1979





HO-113

FRONT STAIRCASE

FROM FRONT HALL #6

BITE THE SKINNER

HOWARD COUNTY

TAKEN BY DONALD B. WARFIELD

APRIL 20, 1979



BITE THE SKINNER  
HOWARD COUNTY

HO-113

LIVING ROOM FIREPLACE # 17

CENTER SECTION MANTEL

HORIZONTAL MOULDINGS MATCH

WINDOW SILL MOULDING IN

LIVING ROOM - TAKEN BY

DONALD B WARFIELD 4-10-79



BITE THE SKINNER

HO-113

HOWARD COUNTY

#8

LIVING ROOM WINDOW - SILL

TRIM MATCHING MANTEL TRIM

TAKEN BY DONALD B WARFIELD

4-10-79





DINING ROOM FIREPLACE # 9

BITE THE SKINNER

HO-113

HOWARD COUNTY

TAKEN BY DONALD B WARFIELD

APRIL 10, 1979



BITE THE SKINNER  
HOWARD COUNTY HO 113

FRONT ENTRANCE FROM  
DINING ROOM #10

TAKEN BY DONALD B.

WARFIELD APRIL 10, 1979



BITE THE SKINNER - HOWARD COUNTY  
FRONT STAIR CASE AND KITCHEN -  
FAMILY ROOM DOOR # 11

TAKEN BY DONALD B. WARFIELD

APRIL 10, 1979

HO-113





STAIR CASE LOOKING UP.

TO. THIRD FLOOR

#12

HC-113

BITE THE SKINNER

HOWARD COUNTY

TAKEN BY DONALD B WARFIELD

4-10-79



BITE THE SKINNER HU 113  
HOWARD COUNTY

SECOND FLOOR LANDING #13  
STAIR CASE DETAIL

TAKEN BY DONALD B WARFIELD

APRIL 10, 1979



BITE THE SKINNER HC-113

HOWARD COUNTY #14


SECOND FLOOR WEST BEDROOM

ORIGINAL MANTEL - RECENTLY

ADDED CLOSET AND BOOK SHELVES

TAKEN BY DONALD B. WARFIELD

4-10-79






BITE THE SKINNER HO-113  
HOWARD COUNTY

SECOND FLOOR EAST BEDROOM

RECENTLY ADDED CLOSETS \$15

AND BOOKSHELVES. TAKEN BY

DONALD B. WARFIELD 4-10-79



BITE THE SKINNER HO-113

HOWARD COUNTY #16

CHIMNEY END THIRD FLOOR

TAKEN BY DONALD B. WARFIELD

4-10-79



BITE THE SKINNER

HO-113

HOWARD COUNTY

#17

THIRD FLOOR DORMER WINDOW

TAKEN BY DONALD B WARFIELD

4-10-79





BITE THE SKINNER HO:13

HOWARD COUNTY

#18

SMOKE HOUSE - FRONT VIEW

TAKEN BY DONALD B. WARFIELD

4-10-79




BITE THE SKINNER HC-113  
HOWARD COUNTY

SMOKEHOUSE BACK VIEW #19

TAKEN BY DONALD B. WARFIELD

4-10-79



H0-113

THE BERNARD WARFIELD HOUSE  
SOUTH WEST

CHEORA THOMPSON, AIP  
AUGUST - 1978



HO. 113

775A

see May '72

Bernard Warfield's house





H.O. 113

775A

see May '72

Bernard Warfield's smokehouse